

Lawton Adams Construction Co.
260 Route 100 Somers, NY 10589
(914) 232-3275

Sieve Analysis Report

Product 1300-Subbase (Fine-3/4")

Period: 01/01/2025 - 08/04/2025

Report Date 08/04/2025

Procedure	Sieve/Test	Result	Unit	Select Granular Material
	4" (100mm)	100	%	
	2" (50mm)	100	%	100-100
	1 1/2" (37.5mm)	100	%	
	1" (25mm)	100	%	
	3/4" (19mm)	86	%	
	1/2" (12.5mm)	60	%	
	1/4" (6.3mm)	56	%	30-65
	1/8" (3.17mm)	49	%	
	#20 (.85mm)	20	%	
	#40 (.425mm)	12	%	5-40
	#80 (.18mm)	7	%	
	#200 (75µm)	3.1	%	0-10